

Index

File No. P-21

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.


N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

|                |  |
|----------------|--|
| CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND                             |
| T4S R32E       | Found a iron monument, set in a mound of stone, with a     |
| 1/4            | brass cap marked as shown in diagram. The monument is      |
| S231S24        | solid and in good shape.                                   |
| 1977           |  |
| (BLM Cap)      | DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND |
|                | Ponderosa Pine, 24" dia., with healed blaze chopped on     |
|                | but no scribing visible, bears N16°25'E, 44.8 ft. This     |
| PHOTO ID DATA  | original bearing tree is still alive and healthy. (Rec:    |
| Photo No.      | N18°E, 45.54 ft).  |
| Filed At       |  |
| Object ID      | Ponderosa Pine, 22" dia., with scribing visible, bears     |
|                | S79°13'W, 38.2 ft. This original bearing tree is alive and |
| PLANE CO-ORD   | healthy. (Org. Rec: S58°E, 59 lks. BLM Rec: S80°W, 38.94   |
| State Zone     | ft.  |
| X              |  |
| Y              | DESCRIBE CORNER LOCATION:                                  |
| Estab. By      | Corner is 2 ft. north of E-W fence. An old N-S road is     |
|                | 23 ft. west.   |

Signature:



Title: Land Surveyor

Date: 10/17/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.  
No work is needed on the monument.  
From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE  
Douglas Fir, 12" dia., bears S33°30'E, 56.3 ft., scribed: 1/4 S24 BT  
5/8"x30" rebar, set approximately 28 ins. in ground, with yellow plastic  
cap marked PLS 2405 bears, N30°45'W, 33.9 ft.  
Measurements to BT and rebar taken with a magnetic compass, declination 20°  
East, and a nylon clad steel tape. Set steel fence post with Land Survey  
Monument (54-9) and Property Boundary (54-2) signs 5' north and south of  
the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT  
scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze  
and Land Survey Monument (54-9) signs on back of each tree as required.  
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 10/17/94  
Certified Cor. Record Prepared?  Yes  No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. P-21

T.4S., R.32E., W.M.