

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. 0-18

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND

T4S R32E

SW1/16

None. Corner established this survey.

S23

1994

PLS 2405

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA

Photo No.

Filed At

Object ID

PLANE CO-ORD

State Zone

X

Y

DESCRIBE CORNER LOCATION:

Estab.By

Corner falls on east slope of P.Pine and D.Fir. N-S draw bottom is 150 ft. east.

Signature:

*Sue Newstetter*

Title: Land Surveyor

Date: 10/31/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.  
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown  
on the DIAGRAM, 24" in the ground.

From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE  
Douglas Fir, 11" dia., bears N32°10'W, 39.7 ft., scribed: SW1/16 S23 BT  
Ponderosa Pine, 12" dia., bears N39°51'E, 32.6 ft., scribed: SW1/16 S23 BT  
Measurements to BT's taken with an Electronic Tacheometer with bearings  
based on the survey control network. Set steel fence post with Land Survey  
Monument (54-9) and Property Boundary (54-2) signs 5' north and west of the  
monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe  
as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and  
Land Survey Monument (54-9) signs on back of each tree as required. Painted  
a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 10/31/94  
Certified Cor. Record Prepared?  Yes  No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. Q-18

T.4S., R.32E., W.M.