

INDEX No. Q-21

History of original corner establishment:

None. Corner established this survey.

DIAGRAM
T4S R32E
S1/16
S23|S24
1994
PLS 2405

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 12" in the ground and raised a mound of stone and earth around the monument.

From Which:

- Ponderosa Pine, 10" dia., bears N41°28'E, 105.7 ft., scribed: S1/16 S24 BT
- Ponderosa Pine, 12" dia., bears S45°07'W, 83.9 ft., scribed: S1/16 S23 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and east of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.



This work was performed by:
Susan E. Newstetter PLS 2405
Witnessed by: Rick Saul and
Rick Pewonka
October 17, 1994

RECEIVED BY
Umatilla County Surveyor
Date 1-95
Rec'd By KK
No. 95-15-B

Office of _____ County of _____ State of _____ I hereby certify that the within instrument was filed in this office for record on the _____ day of _____, 19____ by _____ (COUNTY OFFICIAL) _____ (DEPUTY) Q-21