

USDA FOREST SERVICE
Index

CORNER RECORD (SEARCH)

File No. 0-21
T.4S., R.32E.
Meridian: Willamette

R.D.: N.F.J.D.
N.F.: UMATILLA

Co. Survey No:
County: Umatilla

CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND

T4S R32E

S1/16

S231S24

1994

PLS 2405

None. Corner established this survey.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None. Corner established this survey.

PHOTO ID DATA

Photo No.

Filed At

Object ID

PLANE CO-ORD

State Zone

X


Y

DESCRIBE CORNER LOCATION:

Estab.By

Corner falls on west side of a N-S ridgetop of scattered pine. A road is 150 ft. east.

Signature:



Title: Land Surveyor

Date: 10/17/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the DIAGRAM, 12" in the ground and raised a mound of stone and earth
around the monument. From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Ponderosa Pine, 10" dia., bears N41°28'E, 105.7 ft., scribed: S1/16 S24 BT
Ponderosa Pine, 12" dia., bears S45°07'W, 83.9 ft., scribed: S1/16 S23 BT
Measurements to BT's taken with an Electronic Tacheometer with bearings
based on the survey control network. Set steel fence post with Land Survey
Monument (54-9) and Property Boundary (54-2) signs 5' north and east of the
monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe
as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and
Land Survey Monument (54-9) signs on back of each tree as required.
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 10/17/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. Q-21

T.49., R.32E., W.M.