


Index
File No. R-17
T 4 S R. 32 E
Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____
R.D. Ukiah County Umatilla
N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found 2 1/2" iron pipe with 3 1/4" brass cap (as shown in corner diagram) in mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 12" douglas fir dead brs N68¹/₂⁰ E, 34.1' with scribing visible.
Ponderosa pine sawn stump about 4' high and 32" diam brs N49¹/₄⁰ E, 64.2' with scribing visible.

A 23" ponderosa pine brs S63.3⁰/₄ E, 26.8' with scribing visible.

A 20" douglas fir brs S60¹/₂⁰ W, 22.5' with pitched over blaze.

A 12" douglas fir brs N11⁰ W, 33.7' with pitched over blaze.

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on South slope about 5' West of N-S fence.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Signature
Will R. Wells

Title Land Surveyor Division _____

Headquarters Pendleton, Ore.

Date 6-03-92

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post next to corner with sign 54-9 attached.

Compass declination 18° East.

9

ACCESSORIES : DESCRIBE NEW BT'S, WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing tree established:

A 7" ponderosa pine bears N31 1/4° E, 52.3' scribed T4SR32ES23 BT.

New BT's has a brass washer stamped PLS 1106 nailed to face of blaze.

Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

10

Work Done By W.R. Wells Title Land Surveyor Date 6-03-92 State Registration No. ORLS 1106
or Agency

Certified Cor. Record Prepared ? Yes No Filed At: Umatilla County Surveyor Date 7-92

11

REMARKS

12

Index File No. R-17 T. 4 S. R. 32 E. MM. Tract or Surv. No. Cor. 13

13