

USDA FOREST SERVICE

CORNER RECORD (SEARCH)

Index

File No. S-17

R.D.: N.F.J.D.

Co. Survey No:

T.4S., R.32E.

N.F.: UMATILLA

County: Umatilla

Meridian: Willamette

CORNER DIAGRAM | DESCRIBE CORNER MONUMENT FOUND

T4S R32E

N1/16

None. Corner established this survey.

S271S26

1994

PLS 2405

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO ID DATA

None. Corner established this survey.

Photo No.

Filed At

Object ID

PLANE CO-ORD

State Zone

X

Y

DESCRIBE CORNER LOCATION:

Estab.By

Corner falls on north slope of fir, larch and L.P. Pine.

N-S fence is 2' east. Old N-S Road is 10' west.

Signature:

Sue Newstetter

Title: Land Surveyor

Date: 11/1/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the DIAGRAM, 26" in the ground.

From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Western Larch, 10" dia., bears S37°45'E, 21.7 ft., scribed: N1/16 S26 BT
5/8" x 30" rebar, set 28" in the ground, with yellow plastic cap marked PLS
2405, bears S50°30'W, 8.1 ft.

Measurements to BT and rebar taken with a magnetic compass, declination 20°
East, and a nylon clad steel tape. Set steel fence post with Land Survey
Monument (54-9) and Property Boundary (54-2) signs 5' north and east of the
monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe
as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and
Land Survey Monument (54-9) signs on back of each tree as required.
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Dr. Land Surveyor No. 2405 Date: 11/1/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. S-17

T.4S., R.32E., W.M.