

USDA FOREST SERVICE
Index

CORNER RECORD (SEARCH)


File No. S-18
T.4S., R.32E.
Meridian: Willamette

R.D.: N.F.J.D.
N.F.: UMATILLA

Co. Survey No:
County: Umatilla

CORNER DIAGRAM	DESCRIBE CORNER MONUMENT FOUND
T4S R32E	
NW1/16	None. Corner established this survey.
•	
S26	
1994	
PLS 2405	DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND
	None. Corner established this survey.
PHOTO ID DATA	
Photo No.	
Filed At	
Object ID	
PLANE CO-ORD	
State Zone	
X	
Y	DESCRIBE CORNER LOCATION:
Estab.By	Corner falls on west slope of P.Pine and D.Fir. N-S ridgetop is 200 ft. east.

Signature:



Title: Land Surveyor

Date: 10/31/94

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MON.
Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown
on the DIAGRAM, 26" in the ground.

From Which:

ACCESSORIES: DESCRIBE NEW BT'S, W.O.'S ETC. ESTABL./WORK DONE TO PRESERVE
Ponderosa Pine, 18" dia., bears N69°44'W, 78.9 ft., scribed: NW1/16 S26 BT
Ponderosa Pine, 11" dia., bears N01°08'W, 70.2 ft., scribed: NW1/16 S26 BT
Measurements to BT's taken with an Electronic Tacheometer with bearings
based on the survey control network. Set steel fence post with Land Survey
Monument (54-9) and Property Boundary (54-2) signs 5' north and west of the
monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe
as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and
Land Survey Monument (54-9) signs on back of each tree as required.
Painted a 6" red band above Bearing Trees signs.

Work Done by: Susan E. Newstetter Or. Land Surveyor No. 2405 Date: 10/31/94
Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Survey.

REMARKS

Index File No. S-18

T.4S., R.32E., W.M.