

INDEX No. S-22

History of original corner establishment:

None. Corner established this survey.

DIAGRAM
T4S R32E
NW1/16
•
S25
1994
PLS 2405

Description of Corner Evidence Found:

None. Corner established this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 20" in the ground and raised a mound of stone and earth around the monument.

From Which:

Ponderosa Pine, 14" dia., bears N07°40'W, 49.6 ft., scribed: NW1/16 S25 BT

Ponderosa Pine, 14" dia., bears S82°34'W, 31.2 ft., scribed: NW1/16 S25 BT

Measurements to BT's taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' south and west of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Susan E. Newstetter
OREGON
JULY 26, 1980
SUSAN E. NEWSTETTER
2405

This work was performed by:
Susan E. Newstetter PLS 2405
Witnessed by: Rick Saul and
Rick Pewonka
October 25, 1994

RECEIVED BY
Umatilla County Surveyor
Date 1-95
Rec'd By KK
No. 95-15-B

Renewal Date: 12/31/96

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was
filed in this office for record on the _____ day of _____, 19____
by _____

(COUNTY OFFICIAL)

(DEPUTY)

S-22