

INDEX No. V-17

History of original corner establishment:

This corner was originally established George Pershin, in 1881, under GLO Contract No. 390. Surveyor General Field Notes state:

Set basalt stone 16x14x7 in a mound of stone on south slope for cor to sec 26, 27, 34 & 35.

DIAGRAM  
T4S R32E  
S27|S26  
S34|S35  
1994  
PLS 2405

Description of Corner Evidence Found:

Found a few stones of record size (16x14x7) however found no marks. There are several rockjacks in the area. Unloaded them all and found no marked stone. This corner is lost to fencing.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 20" in the ground and raised a mound of stone, 2 ft. dia. x 1 ft. high around the monument.

From Which:

Ponderosa Pine, 28" dia., bears N81°01'E, 152.6 ft., scribed: T4S R32E S26 BT  
5/8" x 30" rebar, set approx. 28" in the ground, with yellow plastic cap marked PLS 2405 bears:  
N37°12'W, 11.7 ft. (no grooves on rebar)  
S34°22'E, 10.6 ft. (1 groove on rebar)  
S55°56'W, 11.2 ft. (2 grooves on rebar)

Measurements to BT's and rebar taken with an Electronic Tacheometer with bearings based on the survey control network. Set steel fence post with Land Survey Monument (54-9) and Property Boundary (54-2) signs 5' north and east of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT' scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED PROFESSIONAL LAND SURVEYOR

*Susan E. Newstetter*

OREGON  
JULY 26, 1999  
SUSAN E. NEWSTETTER  
2405

Renewal Date: 12/31/96

This work was performed by:  
Susan E. Newstetter PLS 2405  
Witnessed by: Rick Saul and  
Rick Pewonka  
November 3, 1994

RECEIVED BY

Umatilla County Surveyor  
Date 1-95  
Rec'd By KK  
No. 95-15-B

Office of \_\_\_\_\_ County of \_\_\_\_\_ State of \_\_\_\_\_ I hereby certify that the within instrument was filed in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_ by \_\_\_\_\_  
(COUNTY OFFICIAL) (DEPUTY) V-17