

INDEX No. X-17

History of original corner establishment:

This corner was originally established by George Pershin, in 1881, under GLO Contract No. 390. Surveyor General Field Notes state:

Set basalt stone 17x10x8 in mound of stone on south slope for 1/4 sec.cor.

DIAGRAM
T4S R32E
1/4
S34|S35
1994
PLS 2405

Description of Corner Evidence Found:

Found original stone, 17"x16"x8" in bottom of rockjack. The stone is marked 1/4. I believe it is in it's original position.

Description of monument and accessories I established to perpetuate the original location of this corner:

Moving the original corner stone aside I set in it's place a 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, 6" in the ground and raised a mound of stone 4 ft. dia. x 2 1/2 ft. high around the monument. Place the original stone north alongside the monument.

From which:

5/8" x 30" rebar, set in a mound of stone 1 1/2 ft. high x 1 1/2 dia., with yellow plastic cap marked PLS 2405 bears:

- N42°45'W, 10.2 ft. (no grooves on rebar)
- N54°15'W, 12.8 ft. (1 groove on rebar)
- S51°00'E, 10.6 ft. (2 grooves on rebar)
- S51°15'W, 10.6 ft. (3 grooves on rebar)

Measurements to BT's taken with a magnetic compass, declination 20° East, and a nylon clad steel tape. Set steel fence post with Land Survey Monument (54-9) sign 5' north of the monument. Nailed a brass washer stamped PLS 2405 on blaze above BT scribe as taken this survey. Nailed Bearing Tree (54-3) signs above blaze and Land Survey Monument (54-9) signs on back of each tree as required. Painted a 6" red band above Bearing Trees signs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Susan E. Newstetter

OREGON
JULY 26, 1989
SUSAN E. NEWSTETTER
2405

Renewal Date: 12/31/96

This work was performed by:
Susan E. Newstetter PLS 2405
Witnessed by: Rick Saul and
Rick Pewonka
November 3, 1994

RECEIVED BY
Umatilla County Surveyor
Date 1-95
Rec'd By RS
No. 95-15-B

Office of _____ County of _____ x-17
State of _____ I hereby certify that the within instrument was
filed in this office for record on the _____ day of _____, 19____
_____ by _____
(COUNTY OFFICIAL) (DEPUTY)