


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. C-25

History of original corner establishment:

In 1881, under GLO Contract No. 410, George S. Pershin set a stone 14x12x4, from which a 10" Pine bears N34°E, 81 lks. and a 12" Pine bears N38°W, 90 lks.



Description of corner evidence found:

Found original stone, 14x12x4, with "1/4" on west face.

Bearing tree found:

An 18" dead and down double P. Pine with scribing visible "1/4", broken off. Two foot high stump bears N34°E, 81 lks., with "S BT" visible.


Found rotted remains of original BT northwest of corner.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2x30 aluminum capped aluminum pipe rising 16" in mound, with original stone buried on north side. Cap stamped:

New BT's:

- A 5 1/2" D. Fir bears N44 1/2°W, 60.1 ft., scribed 1/4 S1 BT.
- A 13" D. Fir bears S56°W, 150.1 ft., scribed 1/4 S1 BT.



Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6 March 1982. Set metal post 5 ft. north

Compass Declination: 19 1/2°E Witness: G. Arrand of corner.

From 2110-690, go northeasterly on 2110-672 .1 mi. Follow ridge northerly to where it breaks over into Waucup Creek. There is a rock outcropping on the north end of a clearing. Go west down the hill 300 ft. to another clearing. The corner is in the northwest corner of that clearing.

I hereby certify the above described corner monument and/or accessories was established as described on June 7, 1984.



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 10th day of July, 1984
David Krambler by Betty Cochran
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

C-25

☆ GPO-788-276

84-85-m