


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. G-21

History of original corner establishment:

In 1881, under GLO Contract No. 410, George S. Pershin set a stone 18x14x4, from which a 42" Pine bears N87°E, 133 lks.




Description of corner evidence found:

Found 14x10x5 stone with faint "1/4"

Found a 42" P. Pine bearing N87°E, 88.0 ft., blaze and scribing visible.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2"x30" aluminum capped aluminum pipe rising 22" in mound of stones, with original stone in mound. Cap stamped:



New BT's:

A 7" P. Pine bearing S89.5°W, 237.7 ft., scribed 1/4 S11 BT.

Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6, March, 1982. Set metal fence post 7 ft. north of corner.

Compass Declination: 19 1/2° E
Witness: D. Scott

From the intersection of 2110-359 and 2110, go south .1 mi. on 2110. The west BT is on the right side of the road. Corner is east in big clearing up the hill.

I hereby certify the above described corner monument and/or accessories was established as described on May 11, 1984.



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 10th day of July, 1984
David Rumberg by Betty Cochran
 (COUNTY OFFICIAL) (DEPUTY)

G-21