


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1881 by George S. Pershin as follows:

At 40.00 chains north of section corner  $\frac{21}{28} | \frac{22}{27}$ , set basalt stone 20"x12"x8", 15" in ground, in large open glade for  $\frac{1}{4}$  sec. COR marked  $\frac{1}{4}$  on west side. Raised a mound of stone alongside in lieu of pits.



P-13

Description of corner evidence found:

Chaining N0°33'E from section corner  $\frac{21}{28} | \frac{22}{27}$ , at 2,638 ft. I find a stone, 24"x13"x7", with no visible marks, lying on ground alongside a mound of stones. There is a depression in the mound of stones where the corner stone originally sat. I search an area within a 150 foot radius of this point and find no other stones of record size; all are much smaller. I continue chaining N0°33'E and at 5,283 feet I find evidence of section corner  $\frac{16}{21} | \frac{15}{22}$ . 410 feet north of the corner position I find traces of an old road which crosses the line in a glade.

Description of monument and accessories I established to perpetuate the original location of this corner:

In the center of the depression in the mound of stones left by the original corner stone, I set a 2½"x30" galvanized iron pipe with a 3" brass cap attached. The iron pipe is set 15" into the ground. The brass cap is marked: T4S R33E  
I place the original corner stone alongside the iron pipe and build a mound of stones around the pipe to the brass cap from which bears: A 10" ponderosa pine, S35°W, 155.4 ft. scribed "¼ S21, BT" on double blazes. A 20" ponderosa pine, S65°E, 111.6 ft. scribed "¼ S22, BT" on double blazes. De: 20°E.

54-3 and 54-4 signs were placed on both BT's.

I hereby certify the above corner location was perpetuated as hereon described on October 28, 1981. Witness: John T. Hall.



Office of County Surveyor County of Umatilla  
State of Oregon, I hereby certify that the within instrument was filed in this office  
for record on the 27<sup>th</sup> day of December, 1981.  
David J. Harrison by Betty Halls  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
Umatilla County Surveyor  
★ GPO—799-276  
Date 12-31  
Rec'd By BLS  
No. S-1366