


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1881 by George S. Pershin under General Land Office Contract No. 410. Surveyor General Records state:
 Set basalt stone 18 X 8 X 7 ins. for cor. to secs. 33, 34, 3, 4 from which:
 A Pine 8 ins. dia. brs. S 8° W, 102 lks. dist.
 No other trees near.
 Raised mound of stone along side.



No record of subsequent remonumentation was found in county records.

Description of corner evidence found:

Found stone 14" X 8" X 7" with marks in mound of stone, from which:
 A 16" Lodgepole Pine bears S 8° W, 67.3 ft. scribes visible.

(See map of Survey, dated December, 1975)


Description of monument and accessories established to perpetuate the original location of this corner

At corner position I set 2 1/2" X 30" iron pipe with brass cap marked as shown 24" in ground, from which:

New BTs:

- A 8" Lodgepole Pine bears N 61° E, 174.5 ft. marked T4S R33E S34 BT.
- A 20" Lodgepole Pine bears S 78° E, 76.4 ft. marked T5S R33E S3 BT.
- A 8" Lodgepole Pine bears S 31° W, 63.5 ft. marked T5S R33E S4 BT.

Buried stone West and along side pipe.
 Raised mound of stone 3 ft. base to top of cap.
 Set steel fence post 5+ ft. East.



REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

OREGON
 JULY 10, 1934
 DUANE I. GRIFFITH
 644

Brass Washer nailed to BT blazes.
 Used steel tape and magnetic compass with 19°30' East declination.
 Measured to center of all BTs.

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office for record on the day of.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

2-15

Q-889