


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Rufus S. Moore under GLO contract number 451, dated 1882. Surveyor General record states:
 Set basalt stone 9x9x6 ins. 6 ins. in ground for ¼ sec. cor. marked ¼ on N. face from which:
 A pine 27 ins. dia. brs. S65°E 122 lks. dist. marked ¼ S BT
 A pine 24 ins. dia. brs. N10°W 63 lks. dist. marked ¼ S BT

Corner remonumented by Duane I. Griffith, OPLS 644, in 1975. His record states:
 Found BTs and small mound of stone. Did not find marked stone. At record bearing and distance from BTs I set 2½" x 30" iron pipe with brass cap marked as shown (below) 16" in the ground, from which:
 Original BTs:
 A 28" Pine, dead and down, bears S65°E, 80.5 ft., scribes visible.
 A 26" Pine, vigorous, bears N10°W, 41.6 ft., scribes visible.
 New BT:
 A 14" Pine bears S38°W, 71.9 ft. marked ¼ S36 BT.
 Raised mound of stone 5 ft. base to top of cap. Set a steel fencepost 3' East.
 No record of subsequent monumentation found in Umatilla County survey records.



Description of corner evidence found:

Found a 2½" brass cap monument marked as shown in mound of stone.

ORIGINAL BT
 Found a 27 inch diameter Ponderosa Pine N10°W, 41.6 ft. standing, but in poor condition with scribes visible. (Original Southeast BT not identified)

GRIFFITH BT
 Found a 17 inch diameter Ponderosa Pine S38°W, 71.9 ft. live and vigorous with blaze evident.

Distances to existing BTs are to the center of the tree

T4S R33½E
 S 25
 ¼
 S 36
 1975
 OPLS 644

Description of monument and accessories | established to perpetuate the original location of this corner: From the existing found brass cap monument, I take a new Bearing Tree as follows:


New Bearing Tree:
 A 13 inch diameter Ponderosa Pine bears N49°W, 107.30 feet marked ¼ S25 BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs. (Did not identify original Southeast BT)

Set a steel fencepost approximately 5 feet East with land survey monument and property boundary sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on May 3, 1989.

Witnesses: Rick Robinson and Greg Blackman.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 19½° East magnetic declination and the distance are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey Dept County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office for record on the 28th day of June, 1989
David G. Kramlein by Kathleen Ambrose
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

★ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

1-1

Umatilla County Surveyor
 Date 6-89
 Rec'd by JA
 No. 89-59-R

V-23

V-23