


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by Rufus S. Moore under General Land Office Contract No. 451. Surveyor General Records state:
 Basalt stone 9 X 9 X 6 ins. for 1/4 sec. cor. from which:
 A Pine 27" ins. dia. bears S 65° E, 122 lks. dist.
 A Pine 24" ins. dia. bears N 10° W, 63 lks. dist.



No record of subsequent remonumentation was found in county records.

Description of corner evidence found:

Found BTs and small mound of stone.
 Did not find marked stone.

(See map of Survey, dated December, 1975)

Description of monument and accessories I established to perpetuate the original location of this corner

At record bearing and distance from BTs I set 2 1/2" X 30" iron pipe with brass cap marked as shown 16" in ground, from which:

Original BTs:

A 28+ Pine, dead and down, bears S 65° E, 80.5 ft. scribes visible.


A 26" Pine, vigorous, bears N 10° W, 41.6 ft. scribes visible.

New BT:

A 14" Pine bears S 38° W, 71.9 ft. marked 1/4 S36 BT.

Raised mound of stone 5 ft. base to top of cap.

Set steel fence post 3+ ft. East.



REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Handwritten signature of Duane J. Griffith

OREGON
 JULY 10, 1894
 DUANE J. GRIFFITH
 644

Brass Washer nailed to BT blazes.
 Used steel tape and magnetic compass with 19° 30' East declination.
 Measured to center of all BT's.

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of.....

..... by
 (COUNTY OFFICIAL) (DEPUTY)

V-23