


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by Rufus S. Moore under General Land Office Contract No. 451. Surveror General Records state:
Set basalt stone 13 X 12 X 8 ins. for 1/4 sec. cor. from which:
A Pine 10 in. dia. bears N 52° E, 45 lks. dist.
A Pine 30 in. dia. bears N 40° W, 109 lks. dist.



No record of subsequent remonumentation was found in county records.

Description of corner evidence found:

Found NW BT, opened to expose scribes.
NE BT was in the road.
Found a 18" Pine in the SE quadrant of unknown origin, marked 1/4 S.
Scribes appear to have been carved with a knife.

(See map of Survey, dated December, 1975)

Description of monument and accessories established to perpetuate the original location of this corner

At record bearing and distance from the NW BT I set 2 1/2" X 30" iron pipe with brass cap marked as shown 22" in ground, from which:

Original BT:

A 40" Pine bears N 40° W, 71.9 ft., vigorous, scribes visible.


New BT:

A 24" Pine bears N 74° E, 77.4 ft. marked T4S R34E 1/4

S31 BT.

Raised mound of stone 4 ft. base to top of cap.

Set steel fence post 5+ft. South.



REGISTERED
PROFESSIONAL
LAND SURVEYOR

Duane J. Griffith
OREGON
JULY 10, 1934
DUANE J. GRIFFITH
644

Brass Washer nailed to BT blazes.
Used steel tape and magnetic compass with 19° 30' East declination.
Measured to center of all BTs.

Office of..... County of.....
State of....., I hereby certify that the within Instrument was filed in this office
for record on the day of.....
..... by

(COUNTY OFFICIAL) (DEPUTY)