

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: J-13, Northeast corner Section 16, T5N., R28E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set post Cor. to Secs. 9, 10, 15 & 16. Made mound; drove charred stake, as per instructions. Re-established by the US. Engineers, War Department, Portland District, dated October 20, 1947. Record states: No evidence found of original survey. Re-establish corner by calculated tie from Corps of Engineers location of original corner in 1944. Set hub at the edge of ferry road. Maintained by G. Dennis Edwards, Umatilla County Survey #91-01-B. No corner certificate found for Survey #91-01-B.

MONUMENT AND ACCESSORIES FOUND:

Found a 3 1/2" brass cap in concrete 6" below ground, marked as shown in "Monument Marking Detail".

An aluminum tag stamped #951 in North face of RR tie bears S 03°51' E, 20.39 feet.

An aluminum tag stamped #951 in South side of PP&L pole #099001 bears N 25°39' W, 84.08 feet.

MONUMENT MARKING DETAIL:

U.S. ENGINEER DEPARTMENT

PORTLAND DISTRICT

T5N R28E

9 | 10

16 | 15

Boundary Monument

MONUMENT SET:

New Accessories:

A brass washer stamped "PLS 1106", 2.3 feet above ground in south face of RR tie bearing N 05° E, 179.63 feet.

A brass washer stamped "PLS 1106", 3.0 feet above ground in a 12" locust tree bears S 57° W, 71.29 feet.

Corner has steel fence post with witness post sign attached, N 45° W, 1.0 feet.

All accessories have bearing object tags attached.

LOCATION AND COMMENTS:

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells

Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 824814.33

East: 850557.88

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6-30-98

98-101-1