

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: J-15, North 1/4 corner Section 15, T5N., R28E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set 1/4 Sec. post, on top of bluff; made mound; drove charred stake, as per instructions. Reestablished by G. Dennis Edwards, Umatilla County Survey #88-45-C.

MONUMENT AND ACCESSORIES FOUND:

Found a 2 3/8" brass cap, on 1" iron pipe, 6" above the ground, stamped as shown in "Monument Marking Detail".

Found no existing accessories.

MONUMENT MARKING DETAIL:

T5N R28E

1 S10

4 S15

1988

LS 951

MONUMENT SET:

New Accessories:

A 5/8" x 30" iron rod with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", 2" above ground bears N 45° E, 48.46 feet.

A 5/8" x 30" iron rod with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", 2" above ground bears S 54° E, 45.76 feet.

A 5/8" x 30" iron rod with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", 2" above ground bears S 32° W, 52.50 feet.

A 5/8" x 30" iron rod with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", 2" above ground bears N 51° W, 44.38 feet.

Corner has steel fence post with witness post sign attached, South, 1.5 feet.

All accessories have bearing object tags attached and steel fence posts 1.0 feet beyond with witness sign attached.

LOCATION AND COMMENTS:

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells

Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 824849.86

East: 8508230.75

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

98-111-0

Runns 6-30-98