

**OREGON CORNER RESTORATION FORM**

**Section:** 8 - 9 - 17 - 16  
**Township:** 5 North  
**Range:** 28 East of the Willamette Meridian  
**County:** Umatilla  
**Date:** January 2024

**Corner Indexing Information:** Township 5N Range 28E Corner Code J-9 (Willamette Meridian)  
**Additional Identifier:** Corner common to Sections 8, 9, 16 & 17  
**Oregon Plane Coordinates:** N: 824625.88 E: 8500307.58 **Zone:** North **Order:** Second  
**Datum:** NAD83-2011(epoch 2010) **Convergence:** N 00°49'51.71" W **Scale Factor:** .99997051604029

**Previous Renewals/Surveys, etc.:**

1861: Set post, mound, pits, & charred stake (Davenport, General Land Office Contract #101)  
1888: Corner found, not described (Arnold, C.S. 33)  
1907: "The old corner" found, not described (J. Kimbrell, C.S. 251)  
1907: Corner found, not described (J. Kimbrell, C.S. 260)  
1943: Found 2" x 36" iron pipe maintained by locals & Co. Eng. as position of original GLO post; replaced with 2" x 36" iron post 30" deep with brass cap (Price, GLO Special Instructions of 4/3/1943).  
1948: Brass cap reported (Storms, C.S. Q-1543-B)  
1971: Found brass cap (Krumbein, C.S. H-065-AX)  
1991: C.S. 91-01-B Edwards found 1943 brass cap and set 4 new accessories: a power pole with aluminum tag N86°24'W 271.80 feet; a power pole with aluminum tag N02°21'40"W 53.46 feet; a power pole with aluminum tag N64°23'00"E 279.42 feet; a steel post with witness corner sign attached S05°W 2.30 feet.  
1998: C.S. 98-101-C Wells found 1943 brass cap and the 3 power pole accessories per C.S.91-01-B and set 1 new accessory a 5/8"x30" iron rod with plastic cap "OR PLS 1106, WA PLS 17372" S46°E, 88.91 feet.

**Monument(s) & Accessories Found (Condition & Source):**

Found 2-1/2" GLO brass cap dated 1943, flush with ground, +/-27' Southeast of road centerline; utility pole ID # 090001 with witness post sign & bearing tree sign marked "53.46 ft S02°21'40"E Mar. 1990 PLS 951", bears N03°13'46"W, 53.50 feet from the corner.

**Monument Set (Procedures & Description):**

N/A

**Monument Detail:**

GENERAL LAND OFFICE SURVEY  
T5N R28E  
S8 | S9  
S17 | S16  
1943

**New Accessories: WE SET:**

Set bearing object sign on a t-post, bears S50°19'E, 89.62 feet from the corner; Set bearing object sign on a utility pole ID# 089000, bears S85°34'41"W, 271.64 feet from the corner; Set bearing object sign on a utility pole ID# 090007, bears N63°31'01"E, 279.16 feet from the corner; Set bearing object sign on a utility pole ID# 160900, bears S00°10'09"E, 310.71 feet from the corner; Set bearing object sign on a set 5/8" iron rebar with yellow plastic cap stamped "PBS WA19619 OR02820", bears S40°19'49"W, 94.55 feet from the corner.

**Location & Comments:**

Near 3<sup>rd</sup> Street soccer field access to parking lot

**Compass Declination:**

All accessories tied with State Plane grid bearings.

**Firm/Agency:** PBS Engineering & Environmental, Inc.  
5 N. Colville Street  
Walla Walla, WA 99362

**Witness:** Mark F. Wendover  
Eduardo C. Ibarra  
Felipe G. Hernandez  
Hayden J. Lomeli

**Surveyor's Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR



OREGON  
JUNE 30, 1997  
GREG E. FLOWERS  
02820LS

RENEWS 12/31/2025  
1/25/2024