

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: J-9, Northwest corner of Section 16, T5N., R28E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set post Cor. to Secs. 8, 9, 16 & 17; made mound and deposited charred stake, as per instructions. Dependent resurvey by Norman D. Price, under Group No. 278, dated April 3, 1943. Notes state: Set an iron post, 3 ft. long, 2 ins. diam., 30 ins. in the ground, with the iron pipe and broken glass deposited at the base, for cor. of secs. 8, 9, 16 and 17, with brass cap (marked as shown in monument marking detail), raise a mound of stone, 2 ft. base, 1 1/2 ft. high, W. of cor. Surveyed by G. Dennis Edwards #951, 1991. Notes state: Found iron post 3' x 2", 30" in the ground with brass cap (Price). New accessories set: A power pole N86°24'W, 271.80 ft. w/ Alum. Tag #951 attached. A power pole N02°21'40"W, 53.46' w/ Alum. Tag #951 attached. A power pole N64°23'00"E, 279.42' w/Alum. Tag #951 attached. A steel post S05°W, 2.30 ft. w/Witness Corner sign attached. Bearing Object signs attached to all accessories.

MONUMENT AND ACCESSORIES FOUND:

A 2 1/2" brass cap 2" above ground stamped as shown in "monument marking detail".
An aluminum tag stamped #951 in face of PP&L pole #090007 bears N 64°23'00" E, 279.42 feet.
An aluminum tag stamped #951 in face of PP&L pole #089000 bears S 86°24'00" W, 271.80 feet.
An aluminum tag stamped #951 in face of PP&L pole #090001 bears N 02°21'40" W, 53.46 feet.

MONUMENT MARKING DETAIL:

U.S. GENERAL LAND OFFICE SURVEY

T5N R28E
S8 | S9
S17 | S16
1943

MONUMENT SET:

New Accessories:
A 5/8" x 30" iron rod with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears S 46° E, 88.91 feet.
New accessory has steel fence post with witness post sign 1.0 feet South.
Corner has steel fence post with witness post sign attached, S 05° W, 2.3 feet.
All accessories have bearing object signs attached.
All existing accessories have witness post signs attached.

LOCATION AND COMMENTS:

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells
 J.C. Linder

Oregon State Plane Coordinate North Zone, NAD 83(91), Int. Feet:
North: 824625.77
East: 8500307.41

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

98-101-C

Renews 6-30-98