

OREGON CORNER RESTORATION FORM

Section: 14 – 13
Township: 5 North
Range: 28 East of the Willamette Meridian
County: Umatilla
Date: 01/11/2023

Corner Indexing Information: Township 5N Range 28E Corner Code L-21 (Willamette Meridian)

Additional Identifier: Quarter corner between Sections 14 & 13

Oregon Plane Coordinates: N: 822274.43 E: 8516285.26 **Zone:** North **Order:** Second

Datum: NAD83-2011(epoch 2010) **Convergence:** N 00°52'31.61" W **Scale Factor:** 0.99995919923922

Previous Renewals/Surveys, etc.:

1861: Set post, mound, pits, & charred stake (Davenport, General Land Office Contract #101)

Monument(s) & Accessories Found (Condition & Source):

3-1/2" brass cap, in 8" concrete cylinder in 2' diameter concrete slag pile, 10.2' East of Right-of-Way fence on East side of Beach Access Road. Brass cap is 2.5' South of a line of utility poles to the West.

Monument Set (Procedures & Description):

N/A

Monument Detail:

U.S ENGINEER DEPARTMENT
PORTLAND DISTRICT
T5N
R28E
14|13
1/4 COR
BOUNDARY MONUMENT

New Accessories: WE SET:

The Northeast bolt of a fire hydrant base flange, bears N48°28'13"W, 92.68 feet from the corner; Set bearing object sign on a utility pole, bears S33°00'42"W, 121.35 feet from the corner. (2) 5/8"x30" iron rebar with T-post alongside, set bearing object signs on T-posts, accessories bear S42°32'05"E, 90.84 feet & N54°02'17"E, 94.77 feet from the corner.

Location & Comments:

+/- 1150' Northerly from intersection of U.S 730 & Beach Access Road. East side road of Right-of-Way.

Compass Declination:

All accessories tied with State Plane grid bearings.

Firm/Agency: PBS Engineering & Environmental, Inc.
5 N. Colville Street
Walla Walla, WA 99362

Witness: Mark F. Wendover
Eduardo C. Ibarra
Hayden J. Lomeli
Felipe G. Hernandez

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR



OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/2025
1/25/2024