

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: N-11, North 1/4 Corner Section 21, Township 5 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Set 1/4 Sec. post; made mound and drove charred stake, as per instructions. Re-established by J.C. Arnold, Umatilla County Survey No. 33, dated July 14, 1888. Notes state: Set post mkd 1/4 on N. Dependent Resurvey by Frank A. Tuers, under Special Instructions Group No. 864 dated April 11, 1975. Record states: Found it monumented with an iron post, 3 ins. diam., firmly set, 2 ins. below ground, with a brass cap mkd. BONNEVILLE POWER ADMINISTRATION, and an iron rebar, 3/8 in. diam. alongside. This position is harmoniously related with other corners in area, has long been recognized as the cor. by adjacent landowners and private surveyors, and is accepted as the best available evidence of the original 1/4 Sec. Cor. position. At the corner point Set an iron post, 28 inches long, 2 1/2 ins. diam., 21 ins. in ground, with brass cap stamped as shown in "Monument Marking Detail", from which A corner post of fences extending N., E. and W., bears E., 76 lks. dist. Maintained by G. Dennis Edwards, Umatilla County Survey Records #91-01-B, dated January 1991. Record states: Found 3 1/2" B.C. on 2 1/2" iron pipe stamped as shown in "Monument Marking Detail". Found a steel fence post S 88°52' W 2.00 feet. New Accessories: Alum. Tag in RR tie fence post Bears N 67°11' E 54.01 feet. Alum. Tag in Power Pole Bears S 55°44' E 61.57 feet. A steel fence post Bears S 02°38' W 1.25 feet. Attached Bearing Object signs & Warning signs to new accessories and the found steel fence post.

MONUMENT AND ACCESSORIES FOUND:

Found a 3 1/4" brass cap flush with ground stamped as shown in "Monument Marking Detail".

Accessories Found:

An aluminum tag stamped #951 in face of a railroad tie fence corner bears N 67°11' E, 54.01 feet.

An aluminum tag stamped #951 in face of UECA pole #215904 bears S 55°44' E, 61.57 feet.

A steel fence post bears S 02°38' W, 1.2 feet.

A steel fence post bears S 88°52' W, 2.0 feet.

MONUMENT MARKING DETAIL:

U.S. DEPT. OF THE INTERIOR

T5N R28E

1 S16

4 S21

1975

CADASTRAL SURVEY

BUR. OF LAND MANAGEMENT

MONUMENT SET:

All accessories have bearing object and witness post sign attached.

LOCATION AND COMMENTS: Note: Bad location for bearing objects (rock pit).

Through gate East of Bonney Rock Pit Scale then South to East-West fence.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells

Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

North: 819420.58

East: 8503005.95

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

98-101-C

Rmws 6-30-98