

OREGON CORNER RESTORATION FORM

Section: 32 - 33  
Township: 5 North  
Range: 28 East of the Willamette Meridian  
County: Umatilla  
Date: 12/13/22

Corner Indexing Information: Township 5N Range 28E Corner Code X-9 (Willamette Meridian)  
Additional Identifier: Quarter corner between Sections 32 & 33

Oregon Plane Coordinates: N: 8061856.49 E: 8500598.31 Zone: North Order: Second  
Datum: NAD83-2011(epoch 2010) Convergence: N00°49'52"W Scale Factor: 1.000044268448

Previous Renewals/Surveys, etc.:

1861: Set post, mound, pits, & charred stake (Davenport, General Land Office Contract #101)  
1909: NF (J. Kimbrell, C.S. 283)  
1910: NF (J. Kimbrell, C.S. 313)  
2014: Set 3" aluminum cap on 5/8" rebar 2.5' below grade, set by retracement of R.O.S. 08-136-B. Set (4) 5/8" rebars with cap stamped "PLS 61420", N81°02'E 325.20' near pivot base and stand pipe, N38°32'W 522.11' near irrigation valve stand pipe, S25°22'E 1437.86 near old windmill base, S18°29'W 1188.91 near pivot base (King, LCR 14-030-C)

Monument(s) & Accessories Found (Condition & Source):

3" aluminum cap 2.5' deep in a field.

Monument Set (Procedures & Description):

N/A

Monument Detail:

CH3, LLC  
1/4  
S. 32 | S. 33  
2014  
PLS 61420

New Accessories: WE SET:

5/8"x30" iron rebar with yellow cap stamped "PBS WA-19619 OR-02820" which bears N44°59'13"E, 24.99 feet from the corner; bearing tag wired to rebar;  
5/8"x30" iron rebar with yellow cap stamped "PBS WA-19619 OR-02820" which bears N45°00'17"W, 25.02 feet from the corner; bearing tag wired to rebar;  
5/8" iron rebar with yellow cap stamped "PBS WA-19619 OR-02820" which bears S45°02'26"W, 20.00 feet from the corner; bearing tag wired to rebar;  
5/8" iron rebar with yellow cap stamped "PBS WA-19619 OR-02820" which bears S44°58'32"E, 19.9 feet from the corner; bearing tag wired to rebar.

All reference iron rebars are buried 1.5' below grade.

Location & Comments:

Corner lies +-330' Southwesterly from the irrigation pivot and +-1340' Northerly along/from the Northwest corner of a pond South of said pivot.

Compass Declination:

All accessories tied with State Plane grid bearings.

Firm/Agency: PBS Engineering & Environmental, Inc  
5 N. Colville  
Walla Walla WA 99362

Witness: Mark F. Wendover  
Felipe Hernandez  
Hayden Lomeli

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Greg E. Flowers*  
OREGON  
JUNE 30, 1997  
GREG E. FLOWERS  
02820LS

RENEWS 12/31/2025  
02/01/2024