

# OREGON CORNER RESTORATION FORM

SECTION 7

TOWNSHIP 5 NORTH

RANGE 29 EAST

COUNTY: UMATILLA

DATE: 11/21/2022

CORNER DESIGNATION: J-1

PREVIOUS RENEWALS / SURVEYS, etc.

1861: ORIGINAL GLO SURVEY, U.S. DEPUTY SURVEYOR TIMOTHY W. DAVENPORT SET A POST FOR CORNER OF SECTIONS 7, 12, 13 & 18 MADE MOUND AND DEPOSITED CHARRED STAKE AS PER INSTRUCTIONS.

1959: INSTALL DATE OF C.O.E. BRASS CAP IN CONCRETE PER EDWARDS RECORDS

1988: UMATILLA CO. SURVEY 88-045-C, EDWARDS SHOWS FND. & REPAIRED BC IN CONC. MON U.S.

2018: UMATILLA CO. SURVEY 18-043-B, POSADA SHOWS FND. 3-1/2" C.O.E. BRASS CAP IN CONCRETE


2021: UMATILLA CO. SURVEY 21-053-B, BULDOC SHOWS FND. 3-1/2" BRASS CAP IN CONCRETE STAMPED "U.S. ENGINEER DEPARTMENT BOUNDARY MONUMENT PORTLAND DISTRICT"

2022: UMATILLA CO. SURVEY 22-099-B, CATTERSON FND. 3" BRASS CAP IN CONCRETE AS PER CORNER FORM 97-130-R, BY HARMON E. MCLENDON.

MONUMENT and ACCESSORIES FOUND: ( CONDITION AND SOURCE )

2022: FOUND 3-1/2" C.O.E. BRASS CAP IN 6"X6"X24" CONCRETE POST DESTROYED STAMPED AS SHOWN ON SURVEY 18-043-B. POST LEANING SOUTHEAST AND TOP 6" OF POST W/ BRASS CAP LAYING ADJACENT.

DIAGRAM:



MONUMENT and ACCESSORIES SET ( PROCEDURES and DESCRIPTION )

SET STANDARD UMATILLA COUNTY 2-1/4" BRASS CAP ON 1"X30" FLANGED STEEL PIPE ±28" IN THE GROUND IN CONCRETE. STAMPED AS SHOWN ABOVE. BURIED CONCRETE POST REMAINS ±1' SOUTH OF CORNER. REMONUMENTED POSITION BY MID POINT DISTANCE BETWEEN FOUND MONUMENTS NORTH AND SOUTH OF THIS POSITION (RP-1 & RP-3) AND FROM RECORD DISTANCE 340.20 FEET EAST OF RP-5 PER WANAPA SOUTH REPLAT (UM. CO. SURVEY 21-053-B)

REFERENCES SET:

- RP-1 FOUND 5/8"X24" REBAR WITH YELLOW PLASTIC CAP STAMPED "ARMSTRONG SURVEYING" N0°50'49"E 100.00 FEET
- RP-2 FOUND 5/8"X24" REBAR WITH RED PLASTIC CAP STAMPED "PMX CONTROL" N82°05'42"E 770.94 FEET
- RP-3 FOUND 5/8"X24" REBAR WITH YELLOW PLASTIC CAP STAMPED "PARAMETRIX" S0°15'14"W 100.00 FEET
- RP-4 FOUND 5/8"X24" REBAR WITH YELLOW PLASTIC CAP STAMPED "PARAMETRIX" S74°29'20"W 351.30 FEET
- RP-5 FOUND 5/8"X24" REBAR WITH YELLOW PLASTIC CAP STAMPED "PARAMETRIX" N88°58'15"W 340.20 FEET

LOCATION and COMMENTS

MONUMENT LOCATED 1 MILE EAST OF INTERSECTION OF BEACH ACCESS ROAD AND WANAPA ROAD ON SOUTH SIDE WANAPA ROAD. POSITION FALLS ±4.7' SOUTHWESTERLY OF A POWER POLE.

1/4 CORNER BETWEEN SECTIONS 7 AND 18 BEARS N89°28'56"E 2691.63 FEET FROM COMPUTED POSITION.

RECEIVED BY:

UMATILLA COUNTY SURVEYOR

DATE 12/14/22

REC'D BY: CT

NO. 22-137-R

FIRM / AGENCY

ROGERS SURVEYING, Inc., P.S.  
1455 COLUMBIA PARK TRAIL, #201  
RICHLAND, WA 99352  
(509) 783-4141

SURVEYORS SEAL



RENEWS: 06/30/2023

12/05/2022