

OREGON CORNER RESTORATION FORM

SECTION 18 TOWNSHIP 5N RANGE 29E J-3

COUNTY: UMATILLA DATE 7/91
Revised 10/91

CORNER DESIGNATION

North 1/4 Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.


Originally surveyed in 1861 by Davenport under Contract #101.
He set post, made mound and drove charred stake.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Nothing found.

MONUMENT DETAIL

SKETCH



MONUMENT SET (PROCEDURES AND DESCRIPTION)

Dug a hole 8" deep to rock and poured 4" ^{Diam.} concrete cylinder with 3" Brass Disc, stamped as above. (by single proportion)
See Co. Survey #91-058-B.

NEW ACCESSORIES From which

- A 1/2" x 24" rebar with Alum. tag # 951 Bears. N89° 39' 14"W 107.95 ft.
- A 5/8" x 30" rebar with Alum. tag #951, 9" above surface Bears. S89° 39' 14"E 63.85 feet,
- A RR spike stamped #951 Bears. North 14.92 feet,
- A steel fence post with witness sign Bears. South 12.00 feet.
- A 1" x 30" square steel tubing stamped 951 on South face Bears. South 18.88 ft.

LOCATION & COMMENTS

Corner lies S16° E 1400 ft. from the outlet of a 2 foot diameter Aqueduct on the N.E. rim of the Columbia River.

SURVEYOR'S SEAL

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

REGISTERED
PROFESSIONAL
LAND SURVEYOR

J. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor
Date 10-91
Rec'd By RR
No. 91-87-R