

OREGON CORNER RESTORATION FORM

SECTION: 18 TOWNSHIP: 5N RANGE: 29E L-1

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

W 1/4 SECTION 18

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under contract #101 in 1861. He set post and made mound.
In 1988 Co. monumentation survey Edwards computed by single proportion the location in a large pond.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

W.C. Found 2 3/8" B.C.. bears N 0° 06' 14" W 173.48 (173.75')
W. C. Found 1/2" iron rebar with alum. tag 951 bears S 0° 00' 46" W 230.47 (230.57')

MONUMENT DETAIL

T5N
R28E R29E
1/4
S13 S18
1988
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

822235.65
8521557.51

MONUMENT SET (PROCEDURES AND DESCRIPTION)

Nothing set in large pond.

NEW ACCESSORIES FROM WHICH

A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 35° 14' 19" E 280.26'.
A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 23° 28' 34" E 364.74'.

LOCATION AND COMMENTS

On Wanaket Wildlife Area about 2100 feet North of Highway #730.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05