

**OREGON CORNER RESTORATION FORM**

SECTION: 15 TOWNSHIP: 5N RANGE: 29E L-13

COUNTY: UMATILLA DATE: 12/05

**CORNER DESIGNATION**

West 1/4 Section 15

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

**PREVIOUS RENEWALS/SURVEYS ETC.**

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.  
Wayne Harris set 5/8" Iron Rebar in 1968  
Krumbein showed 5/8" Iron Rebar in 1975 survey for Conforth  
Edwards reset 5/8" Iron in 1985 using Krumbein's 1975 survey.

**MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE**

Found 5/8" Iron Rebar 4" below the surface of a cultivated field

**MONUMENT DETAIL**

T5NR29E  
1/4  
16 15  
2005  
L.S. 951

**OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:**

822446.90  
8537477.02

**MONUMENT SET (PROCEDURES AND DESCRIPTION)**

In place of 5/8" iron rebar I set in concrete a 1" x 30" Iron Pipe with a 2 3/8" Brass Cap 18 inches below the surface of a cultivated field stamped as above.

**NEW ACCESSORIES FROM WHICH**

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 28° 48' 47" E 62.71'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 34° 57' 27"W 54.65'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 84° 45' 38" W 441.70'.
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 57° 22' 42" W 339.54'.

**LOCATION AND COMMENTS**

From the Intersection of Salmon Point Drive with Highway # 730, go Northerly on Salmon Point Drive one mile. Corner lies about 400' East of road in the North edge of a center pivot field.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC  
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH  
WITNESS: J. JOSEPH

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RENEWS 12/31/05

06265-C