

**OREGON CORNER RESTORATION FORM**

SECTION: 15 TOWNSHIP: 5N RANGE: 29E L-17

COUNTY: UMATILLA DATE: 12/05

**CORNER DESIGNATION**

*East 1/4 Section 15*

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

**PREVIOUS RENEWALS/SURVEYS ETC.**

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. There was a 3 1/2" Brass Cap set by US Army Corps of Engineers in 1974 but it was not stamped as the 1/4 corner

**MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE**

**Nothing found**

For a W.C. Found a 3 1/2" Brass Cap in concrete. It bears S 19° 14' 18" E 82.17'.

**MONUMENT DETAIL**

T5NR29E  
1/4  
15 14  
2005  
L.S. 951

**OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:**

822515.48  
8542760.62

**MONUMENT SET (PROCEDURES AND DESCRIPTION)**

By single proportion I set a 1" x 30" Iron Pipe with 2 3/8" Brass Cap stamped as detail 4" above the surface. Placed rocks around

**NEW ACCESSORIES FROM WHICH**

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 17° 58' 54" E 26.64'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 89° 48' 33"W 20.00'
- A 1" x 30" iron pipe in concrete with a 2 3/8" brass cap stamped W.C.bears N 69° 26' 10" E 50.00'.

**LOCATION AND COMMENTS**

From the picnic area of Hat Rock State Park go approximately 1200' Easterly along the bottom of a draw to the corner.

SURVEYOR'S SEAL

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RENEWS 12/31/05

FIRM: EDWARDS SURVEYING LLC  
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH  
WITNESS: J. JOSEPH