

OREGON CORNER RESTORATION FORM

SECTION: 17 TOWNSHIP: 5N RANGE: 29E L-9

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

East 1/4 Section 17

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. In 1991 Edwards set 1" x 30" Iron Pipe with 2 3/8" Brass cap.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Found 2 3/8" Brass Cap 3" above ground stamped as Detail.
W.C. 1/2" Iron Rebar with alum. tag 951 bears N 89° 35' 34" W 9.49'.
W. C. 5/8" Iron Rebar with alum. tag 951 bears S° 89 55' 13" E 12.84' (12.89')

MONUMENT DETAIL

T5NR29E
1/4
17 16
1991
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

822292.72
8532191.42

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 16° 18' 56" E 34.54'
A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 16° 59' 27" W 28.34'

LOCATION AND COMMENTS

From the Intersection of Craig Road and Highway #730, go East on Highway #730 one mile. Corner lies approximately 4,500 feet North of highway.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05