

**OREGON CORNER RESTORATION FORM**

SECTION: 23 TOWNSHIP: 5N

RANGE: 29E

N-21

COUNTY: UMATILLA

DATE: 12/05

**CORNER DESIGNATION**

*NE Section 23*

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

**PREVIOUS RENEWALS/SURVEYS ETC.**

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. In 1949 Stranix found old stake in mound of stone. Set concrete monument.

**MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE**

Found 2 5/8" brass cap in a 4" concrete monument stamped as below, 4" above the surface.

**MONUMENT DETAIL**

T5N  
 14 | 13  
 23 | 24  
 R29 E

**OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:**

820021.84  
8548116.67

**MONUMENT SET (PROCEDURES AND DESCRIPTION)**

**NEW ACCESSORIES FROM WHICH**

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 87° 04' 20" E 45.14'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 5° 08' 21" W 33.77'
- A 5/8 x 30 Iron Rebar with plastic cap #951 bears S 89° 26' 41"W 137.78'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 3° 48' 33" E 36.02'

**LOCATION AND COMMENTS**

From the truck scales on hwy 730 go South - Southwest 0.4 miles to corner.

SURVEYOR'S SEAL

**FIRM: EDWARDS SURVEYING LLC  
PO BOX 763 - HERMISTON OR 97838**

**PARTY CHIEF: R. SMITH  
WITNESS: J. JOSEPH**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RENEWS 12/31/05