

OREGON CORNER RESTORATION FORM

SECTION 19 TOWNSHIP 5N RANGE 29E N-5

COUNTY: UMATILLA DATE 7/91
Revised 10/91

CORNER DESIGNATION

NE Corner

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 SURVEYED IN
 REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS, ETC.


Originally surveyed in 1861 by Davenport under Contract #101.
He set post, made mound and drove charred stake.

MONUMENTS & ACCESSORIES FOUND: Condition and Source

Found neat mound of stone 2 ft. diameter and 10 inches high.

MONUMENT DETAIL

SKETCH



MONUMENT SET (PROCEDURES AND DESCRIPTION)

Hollowed out a 6" hole in center of mound, filled with conc. and placed a 2 1/2" Brass Disc, stamped as above.
See Co. Survey #91-058-B.

NEW ACCESSORIES From which

- A P.K. nail in a round hole 4 ft. up on a 10 ft. rock face Bears. S70° 54'E 5.42 feet,
- A 5/8" x 30" rebar with Alum. tag #951 Bears. West 17.22 feet,
- A steel fence post with witness sign Bears. North 5.0 feet,
- A steel fence post with witness sign and bearing sign Bears. South 53.3 ft.
- A 1/2" x 24" rebar with Alum. tag #951 Bears. North 12.79 feet.
- A 1 1/2" washer stamped 951 glued 3 ft. up on an 8 ft. rock face Bears.
- N 62°36' E 8.24 feet.

LOCATION & COMMENTS

From intersection of Craig Rd. & Hwy. #730, go North 550 feet, then West 100 feet to West side of a Rock Bluff.

SURVEYOR'S SEAL

COMPASS DEC.
FIRM EDWARDS SURVEYING
P.O. BOX 763, HERMISTON,
OREGON, 97838
PARTY CHIEF D. EDWARDS
NOTES
WITNESS S. BENEFIT

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RECEIVED BY

Umatilla County Surveyor
Date 10-91
Rec'd By KE
No. 91-88-R