

OREGON CORNER RESTORATION FORM

SECTION:24 TOWNSHIP: 5N

RANGE: 29E

P-25

COUNTY: UMATILLA

DATE: 12/05

CORNER DESIGNATION

E1/4 Section 24

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Payne under Contract # 100 in 1861. He set stake and made mound. In 1949 Stranix found old stake.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Nothing found.

MONUMENT DETAIL

T5N
R29E R30E
1/4
24 | 19
2005
951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

817385.58
8553386.98

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set a 1'x12" iron pipe in concrete with a 2 3/8 brass cap stamped as above, 25" below the surface of a cultivated field.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 34° 23' 33" E 976.40'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 88° 45' 43" W 151.67'
- A 5/8 x 30" Iron Rebar with plastic cap #951 bears S 11° 19' 00" W 770.17'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 23° 32' 37" E 1526.06'

LOCATION AND COMMENTS

From intersection at Cold Springs hwy with Walls rd go SW on Walls 0.9 miles. Then go clockwise Northwesterly around irrigation circle 0.5 miles. Corner lies 150' into large irrigation circle

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05