

**OREGON CORNER RESTORATION FORM**

SECTION: 30 TOWNSHIP: 5N

RANGE: 29E

R-1

COUNTY: UMATILLA

DATE: 12/05

**CORNER DESIGNATION**

NW Section 30

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

**PREVIOUS RENEWALS/SURVEYS ETC.**

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. In 1910 Kimbrell set 2" iron pipe.

In 1984 Krumbein found 2" iron pipe & replaced with 1"x30" iron pipe with 2 3/8" brass cap.

**MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE**

Found 2 3/8" brass cap 10" below the surface of a road stamped as detail.

**MONUMENT DETAIL**

T5N  
R28E S24 | S19 R29E  
S25 | S30  
1984  
R.S. 933

**OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:**

814258.99

8521689.87

**MONUMENT SET (PROCEDURES AND DESCRIPTION)**

**NEW ACCESSORIES FROM WHICH**

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 88° 41' 30" E 16.93'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 45° 10' 54" W 33.97'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 21° 05' 18" E 49.62'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 34° 48' 13" W 64.29'

**LOCATION AND COMMENTS**

At the intersection of Ott Rd & Progress Rd.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC  
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH  
WITNESS: J. JOSEPH

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RENEWS 12/31/05