

OREGON CORNER RESTORATION FORM

SECTION 21, 28 TOWNSHIP 5 NORTH RANGE 29 EAST
COUNTY : UMATILLA DATE DEC/22

R-11

CORNER DESIGNATION
1/4 CORNER

CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNCOVERED
 SURVEYED IN
 REFERENCED


PREVIOUS RENEWALS / SURVEYS, ETC.

SURVEYED IN 1861 BY DAVENPORT UNDER CONTRACT #101, HE SET POST AND MADE MOUND.
IN 1910 KIMBRELL SET 2" IRON PIPE.
IN 1980 LS 951 SET 5/8" IRON ROD INSIDE IRON PIPE, IN 1991 LS 951 SET 2 3/8" BRASS CAP.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

FOUND 2 3/8" BRASS CAP STAMPED AS BELOW.
FOUND 5/8" IRON ROD WITH PLASTIC CAP STAMPED LS 951 BEARS N 64°02'06" E, 64.84'.
FOUND 5/8" IRON ROD WITH PLASTIC CAP STAMPED LS 951 BEARS S 15°13'57" W, 71.35'.
FOUND ALUMINUM TAG IN RAIL ROAD TIE STAMPED LS 951 BEARS S 80°01'9" E, 76.03'.

MONUMENT DETAIL



N.T.S

NAD 83/91
OREGON STATE PLANE
INTERNATIONAL FEET

814459.33
8534963.79

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

SET 5/8" X 30" IRON ROD WITH YELLOW PLASTIC CAP BEARS S 18°02'47" E, 39.73'.

LOCATION AND COMMENTS

CORNER FALLS AT INTERSECTION OF
GOLDA ROAD AND PROGRESS ROAD.

FIRM/AGENCY

PRIMM LAND SURVEYING, INC.
P.O. BOX 1322
HERMISTON, OREGON 97838

LAND SURVEYOR

BRIT L. PRIMM

WITNESS

KEITH P. PRIMM

SURVEYOR'S SEAL

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 13, 1999
BRIT L. PRIMM
48509

EXPIRATION DATE: 12/31/24