

OREGON CORNER RESTORATION FORM

SECTION:28 TOWNSHIP: 5N RANGE: 29E R-13

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

NE Section 28

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. R/R spike of common report at road intersection used for many years by surveyors. Origin unknown.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Found R/R spike

MONUMENT DETAIL

T5NR29E
21 | 22
28 | 27
2005
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

814520.57
8537610.71

MONUMENT SET (PROCEDURES AND DESCRIPTION)

Removed R/R spike & drove 5/8x30" iron rebar with a 2" aluminum cap stamped as above flush with a paved road

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 2° 20' 13" E 20.70'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 56° 24' 26" W 37.01'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 43° 39' 21" W 36.39'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 35° 35' 48" E 25.86'

LOCATION AND COMMENTS

At the intersection of Progress road with Tabor road.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05