

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 6/14/00

CORNER DESIGNATION: R-21, Northeast corner of Section 26, Township 5 North, Range 29 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.

Most recent GLO survey was made by Timothy W. Davenport, Deputy Surveyor, under contract No. 101 dated August 5, 1861. Original notes call for mound and driven charred stake. Corner was re-established by double proportion on Survey M-87-B. This survey calls for a set "B.C.", (brass cap).

MONUMENT AND ACCESSORIES FOUND:

Section corner monument is destroyed by farming. Re-established corner by distance-distance measurement, holding record dimensions per Survey No. M-87-B, from the reestablished Southeast corner of Section 26 and the found Northeast corner of Section 24.

MONUMENT MARKING DETAIL:

T5N R29E
S23|S24
S26|S25
2000
PLS 1106

MONUMENT SET:

Set 2 1/2" brass cap on 1 1/4" x 30" galvanized iron pipe, 15 inches below ground surface, marked as shown in marking detail, from which:

- A silver magnetic "Deep One" marker bears N 42° E, 31.0 feet.
- A purple magnetic "Deep One" marker bears S 50° E, 30.7 feet.
- A blue magnetic "Deep One" marker bears S 43° W, 32.5 feet.
- An orange magnetic "Deep One" marker bears N 44° W, 30.4 feet.

Magnetic markers are buried approximately 15 inches below surface of ground. There is a "bearing object" tag buried with each of the magnetic markers.

LOCATION AND COMMENTS:

Corner falls in alfalfa field. There is a "witness corner" sign nailed to "H" brace in fence N 00 3/4° W, 390 feet from corner.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells
Kevin Snively

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

00-158-C