

OREGON CORNER RESTORATION FORM

SECTION:20 TOWNSHIP: 5N RANGE: 29E

R-5

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

SW Section 20

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. In 1910 Kimbrell set 2" iron pipe.

In 1991 Edwards set a 1"x 3" iron pipe in concrete with a 2 3/8" brass cap over the 2" iron pipe.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Found 2 3/8" brass cap 12" below the surface of a road. Stamped as below.

W.C. an alum. tag 951 in a RR tie fence post bears N 71° 41' 13" E 51.12' (51.46')

W.C. an alum. tag 951 in a RR tie fence post bears S 54° 28' 01" W 35.37' (35.18')

MONUMENT DETAIL

T5NR29E
19 | 20
30 | 29
1991
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

814376.09
8527006.38

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 4° 29' 16" W 48.05'

A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 59° 06' 25" E 50.47'


LOCATION AND COMMENTS

At the intersection of Craig Rd & Progress Rd.


SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH



G. Dennis Edwards



RENEWS 12/31/05