

**OREGON CORNER RESTORATION FORM**

SECTION:30    TOWNSHIP: 5N    RANGE: 29E    T-1

COUNTY: UMATILLA    DATE: 12/05

**CORNER DESIGNATION**

*W1/4 Section 30*

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

**PREVIOUS RENEWALS/SURVEYS ETC.**

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. In a 1988 county monumentation survey Edwards set 1"x30" iron pipe with a 2 3/8" brass cap stamped as below.

**MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE**

Found 2 3/8" brass cap stamped as below 10" below the surface of a graveled road.  
W.C. an aluminum tag #951 in a R/R tie fence post bears S 49° 15' 22" W 31.87'(31.90')  
W.C. an aluminum tag #951 in a R/R tie fence post bears N 45° 30' 40" W 34.37'(34.35')

**MONUMENT DETAIL**

T5N  
R28E R29E  
1/4  
S25 | S30  
1988  
L.S 951

**OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:**

811632.66  
8521731.97

**MONUMENT SET (PROCEDURES AND DESCRIPTION)**

**NEW ACCESSORIES FROM WHICH**

A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 71° 57' 35" E 33.05'  
A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 34° 31' 06" E 54.59'

**LOCATION AND COMMENTS**

From the intersection of Walls road with Ott road, go North on Ott road 0.5 miles to corner.

SURVEYOR'S SEAL

**FIRM: EDWARDS SURVEYING LLC  
PO BOX 763 - HERMISTON OR 97838**

**PARTY CHIEF: R. SMITH  
WITNESS: J. JOSEPH**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*G. Dennis Edwards*

OREGON  
JULY 16, 1971  
G. DENNIS EDWARDS  
951

RENEWS 12/31/05