

OREGON CORNER RESTORATION FORM

SECTION:30 TOWNSHIP: 5N RANGE: 29E T-5

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

E1/4 Section 30

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.
In 1910 Kimbrell set 1 1/2" iron pipe.
In 1992 Edwards drove a 1/2" iron rebar into Kimbrells iron pipe.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Found a 1/2" iron rebar in concrete 3" below the surface of a paved road.

MONUMENT DETAIL

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

811736.90
8527052.92

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 65° 21' 46" E 36.26'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 38° 29' 24" W 45.75'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 15° 17' 32" W 121.68'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 26° 46' 36" E 41.48'

LOCATION AND COMMENTS

At the intersection of Craig and Spearman road.

SURVEYOR'S SEAL

**FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838**

**PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH**

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05