

OREGON CORNER RESTORATION FORM

SECTION:33 TOWNSHIP: 5N RANGE: 29E V-13

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

NE Section 33

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. In 1971 Thompson set a 2 1/2" brass cap.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Found 5/8" iron rebar 4" below the surface of a paved road.
W.C. a 2 1/2" brass cap stamped as below bears N 45° 11' 57" W 46.58' (46.66')

MONUMENT DETAIL

T5NR29E
 28 | 27
 33 | 34
 N45W 46.66
 1971

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

809243.53
8537704.37

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 5° 51' 49" E 183.91'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 33° 31' 25" E 31.20'
- A 5/8 x 30" Iron Rebar with plastic cap #951 bears S 16° 44' 05" W 62.34'


LOCATION AND COMMENTS

At the intersection of Tabor road and Walls road.


SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH



G. Dennis Edwards



RENEWS 12/31/05