

OREGON CORNER RESTORATION FORM

SECTION:34 TOWNSHIP: 5N RANGE: 29E V-15

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

N1/4 Section 34

 CONDITION REPORT ONLY
 NOT FOUND
 RENEWED
 UNRECORDED
 X **SURVEYED IN**
 X **REFERENCED OUT**

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Nothing found.

MONUMENT DETAIL

T5NR29E
1/4 27
34
2005
L.S.951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

809282.48
8540347.58

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set a 1"x30" iron pipe in concrete with a 2 3/8" brass cap stamped as above 3" below the surface of a paved road on the South shoulder.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 59° 21' 11" E 63.23'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 34° 51' 40" W 40.23'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 87° 27' 49" W 222.90'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 77° 50' 31" E 33.62'

LOCATION AND COMMENTS

From the intersection of Tabor road with Walls road go East on Walls 0.5 mile to corner.

SURVEYOR'S SEAL

**FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838**

**PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH**

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05