

OREGON CORNER RESTORATION FORM

SECTION: 27 TOWNSHIP: 5N RANGE: 29E V-17

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

SE Section 27

- CONDITION REPORT ONLY*
- NOT FOUND*
- RENEWED*
- UNRECORDED*
- SURVEYED IN*
- REFERENCED OUT*

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. In 1981 Edwards set a 1" x30" iron pipe with a brass cap stamped as below from R/R ties.

MONUMENTS AND ACCESSORIES FOUND: CONDITON AND SOURCE

Found 2 1/2" brass cap stamped as below 4" below the surface of a graveled road.

MONUMENT DETAIL

T5NR29E
27 | 26
34 | 35
1981
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

809321.42
8542990.78

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 73° 47' 52" E 92.38'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 44° 17' 14" W 13.59'
- A 5/8 x 30 Iron Rebar with plastic cap #951 bears S 11° 13' 52" W 53.86'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 73° 26' 49" E 191.34'

LOCATION AND COMMENTS

At the intersection of Marks road with Walls road corner lies at the NW corner of intersection.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05