

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 6/14/00

CORNER DESIGNATION: V-21, Southeast corner of Section 26, Township 5 North, Range 29 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.

Most recent GLO survey was made by Timothy W. Davenport, Deputy Surveyor, under Contract No. 101 dated August 5, 1861. Original notes call for mound and driven charred stake. Corner was re-established and monumented with "brass cap" monument on Survey No. J-92-A, and has been used on all record surveys since.

MONUMENT AND ACCESSORIES FOUND:

Section corner monument is destroyed by farming. Re-established corner at record angle and distance from Northeast corner of Tract surveyed on Survey No. M-88-B, using Northwest corner of Tract as backsight.

MONUMENT MARKING DETAIL:

T5N R29E
S26|S25
S35|S36
2000
PLS 1106

MONUMENT SET:

Set 2 1/2" brass cap on 1 1/4" x 30" galvanized pipe 15 inches below ground surface, marked as shown in marking detail, from which:

- A 5/8" iron rebar bears N 82°22'41" E, 91.47 feet.
- A 5/8" iron rebar bears S 00°12'39" E, 9.21 feet.
- A 5/8" iron rebar bears S 00°12'39" E, 70.26 feet.
- A 5/8" iron rebar bears S 77°54'50" W, 131.47 feet.

5/8" iron rebars used as references are monuments set and reported on the Survey Map accompanying this corner restoration form. Rebars are capped with 1 1/2" yellow plastic caps marked "OR PLS 1106, WA PLS 17372."

LOCATION AND COMMENTS: Corner located north of East Walls Road, just North of East x West fence. There is a "witness corner" sign on railroad tie fence post near the corner.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells
Kevin Snively

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 23, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

00-158-C