

OREGON CORNER RESTORATION FORM

SECTION: 25 TOWNSHIP: 5N RANGE: 29E V-23

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

S1/4 Section 25

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Nothing found

MONUMENT DETAIL

T5NR29E
1/4 25
36
2005
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

809439.28
8550897.28

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set a 1"x12" iron pipe in concrete 25" below the surface of a cultivated field.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 21° 21' 53" E 1684.67'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 11° 01' 00" W 360.55'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 39° 54' 11" W 1691.53'
- A concrete nail in a pivot pad bears N 9° 29' 23" W 367.92'

LOCATION AND COMMENTS

From an angle point in Walls road go East 0.5 miles to a point which lies 360' south of a center pivot.

SURVEYOR'S SEAL

**FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838**

**PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH**

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
951

RENEWS 12/31/05