

OREGON CORNER RESTORATION FORM

SECTION: 25 TOWNSHIP: 5N RANGE: 29E V-25

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

SE Section 25

- CONDITION REPORT ONLY**
- NOT FOUND**
- RENEWED**
- UNRECORDED**
- SURVEYED IN**
- REFERENCED OUT**

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Payne under Contract # 100 in 1861. He set post and made mound.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Nothing found.

MONUMENT DETAIL

T5N
R29E R30E
25 | 30
36 | 31
2005
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

809465.36
8553541.12

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set a 1"x12" iron pipe in concrete with a 2 3/8" brass cap stamped as above, 25" below the surface of a cultivated field.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 84° 31' 21" E 1272.23'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 14° 04' 04" E 1635.77'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 19° 45' 37" W 1715.63'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 47° 59' 45" W 1723.88'

LOCATION AND COMMENTS

From an angle point in Walls road go East 1.0 miles. Corner lies about 200' Northeast of a center pivot.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
9 5 1

RENEWS 12/31/05