

OREGON CORNER RESTORATION FORM

SECTION:31 TOWNSHIP: 5N

RANGE: 29E

V-3

COUNTY: UMATILLA

DATE: 12/05

CORNER DESIGNATION

N1/4 Section 31

- CONDITION REPORT ONLY*
- NOT FOUND*
- RENEWED*
- UNRECORDED*
- SURVEYED IN*
- REFERENCED OUT*

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Nothing found

MONUMENT DETAIL

T5NR29E
 1/4 30
 31
 2005
 L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

809053.94
 8524457.02

MONUMENT SET (PROCEDURES AND DESCRIPTION)

By single proportion I set a 1"x25" iron pipe in concrete with a 2 3/8" brass cap stamped as above, 6" below the surface of a graveled road.

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 29° 17' 13" W 43.77'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 49° 29' 56" W 29.80'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 85° 13' 45" W 165.91'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 62° 25' 50" W 26.76'

LOCATION AND COMMENTS

From the intersection of Craig road with Walls road go west on Walls road 0.5 miles to corner.

SURVEYOR'S SEAL

**FIRM: EDWARDS SURVEYING LLC
 PO BOX 763 - HERMISTON OR 97838**

**PARTY CHIEF: R. SMITH
 WITNESS: J. JOSEPH**

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

G. Dennis Edwards

OREGON
 JULY 16, 1971
 G. DENNIS EDWARDS
 951

RENEWS 12/31/05