

OREGON CORNER RESTORATION FORM

SECTION: 25 TOWNSHIP: 5N RANGE: 29E R-25

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

NE Section 25

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Payne under Contract # 100 in 1861. He set post and made mound. In 1970 Harris set a 1"x36" iron pipe with brass cap.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Found 2 1/2" brass cap 22" below the surface of a cultivated field stamped as below.

MONUMENT DETAIL

RLS346
R29E
24 | 19
25 | 30
T5N R30E

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

814745.66
8553439.00

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 79° 20' 15" E 198.33'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 68° 41' 31" W 999.31'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 12° 04' 52" W 214.44'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 88° 38' 55" E 235.64'


LOCATION AND COMMENTS

From the intersection of Cold Springs highway with Walls road go Southwest on Walls road 1.35 miles. Corner lies approximately 150' Northwest of road.


SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH



G. Dennis Edwards



RENEWS 12/31/05