

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 07/06/10

CORNER DESIGNATION: J-23, The North 1/4 corner of Section 13, Township 5 North, Range 33 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by Odell & Lewis under Contract No. 110 dated February 7th, 1865. Notes state: Set 1/4 section post, drove charred stake, dug pits, raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None

MONUMENT MARKING DETAIL:

T5N R33E

1 S12

4 S13

2010

PLS 1106

MONUMENT SET: At a point 6 inches West of a lone locust post in a field corner with field lines east-west and south, held as best evidence of original corner location, set a 2 3/8" diameter brass cap on a 1 1/4" x 30" galvanized iron pipe, with top of brass cap at ground surface and stamped as shown in "Monument Marking Detail".

New accessories:

- A silver "deep-1" magnet buried 18" in the ground bears N 55° E, 28.6 feet.
- A blue "deep-1" magnet buried 18" in the ground bears S 43° E, 32.3 feet.
- A pink "deep-1" magnet buried 18" in the ground bears S 47° W, 33.4 feet.
- An orange "deep-1" magnet buried 18" in the ground bears N 46° W, 33.1 feet.

Nailed Witness sign to locust post.

Buried bearing object sign with each of the "deep 1" magnet accessories.

LOCATION AND COMMENTS: Set in line with field berms to the south and east-west. A steel tape and magnetic compass were used to measure bearings and distances to accessories.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 827494.61

E = 8677859.45


FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells
Dean Roy

5N33J23



Will R. Wells



renews 6-30-12

RECEIVED BY
Umatilla County Surveyor
Date: 4/3/2012
Rec'd By: *Darryl Nelson*
No.: 12-0291-C