

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 07/02/10

CORNER DESIGNATION: N-23, The 1/4 corner common to Section 13 and Section 24, Township 5 North, Range 33 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by Odell & Lewis under Contract No. 110 dated February 7th, 1865. Notes state: Set 1/4 sec post, drove charred stake, dug pits & raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None

MONUMENT MARKING DETAIL:

T5N R33E
1/4 S13
S24
2010
PLS 1106

MONUMENT SET: Held intersection of centerline of Duroc County Road with old field berm extending south and north as best remaining evidence of the original corner location. Set a 2-3/8" diameter brass cap on a 1 1/4" x 30" galvanized iron pipe, with top of brass cap 6" below gravel road surface and stamped as shown in "Monument Marking Detail".

New accessories:

- A 5/8" by 24" rebar with 1 1/4" red plastic cap bears N 62° E, 32.2 feet.
- A 5/8" by 24" rebar with 1 1/4" red plastic cap bears S 03° W, 15.2 feet.
- A 5/8" by 24" rebar with 1 1/4" red plastic cap bears S 78° W, 58.9 feet.
- A 5/8" by 24" rebar with 1 1/4" red plastic cap bears N 61° W, 48.9 feet.

Nailed a "witness" sign to a rail road tie post at south edge of road.

Red plastic caps on rebar accessories are marked "OR PLS 1106 WA PLS 17372". The rebar accessories are set near road shoulder. Wired a bearing object sign to each of the rebar accessories.

LOCATION AND COMMENTS: Corner is located at a point in the centerline of Duroc Road and a farmed field berm to the south and a fainter field berm to the north. A steel tape and magnetic compass were used to measure bearings and distances to accessories.


OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:
N = 822011.57
E = 8678070.97

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801


COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells
Dean Roy



William R. Wells



renews 6-30-12

5N33N23

RECEIVED BY
Umatilla County Surveyor
Date: 4/3/2012
Rec'd By: Dan Kubit
No.: 12-029-c